



BILL OF MATERIAL

NO. TO SHIP	TOTAL	PCS	DESCRIPTION	LENGTH	REMARKS	QTY	WEIGHT
MARK	MARK			IN.		UNIT	TOTAL
ONE SPA-2			FRAME ASSY				
	ONE	2a	1/4" X 6"	11	A36 - ROLLED		
	ONE	2b	1/4" X 6"	11	A36 - ROLLED		
	6	c	1/4" X 1 1/2"	0	A36		
	ONE	2d	1/4" X 2 1/2"	0	A36 - ROLLED		
	ONE	2f	1/4" X 2 1/2"	0	A36 - ROLLED		
			FIELD HARDWARE				
		b1	1/4" SS CAP SCREW	0	TCR24244A543		
		b2	1/4" SS ACORN NUT	0	TCR1955A370		
		b3	1/4" SS FLAT WASHER	0	TCR1955A030		
		b4	3/8" NYLON BUSHING	0	TCR438K348		
		b5	3/8" SS TECH SCREW	0	TCR1771A619		
		b6	1/4" GASKET MATERIAL	23	LN FT.		

FABRICATION NOTES:

HOLES UNO: 5/8"
 WELD:
 REF DWG: DE-1A
 MATERIAL UNO: LAMINATED GLASS
 PAINT: Copper Penny - 818-8

NOTES:
 VERIFICATION OF DIMENSIONS, DETAILS, AND ETC. ARE REQUESTED, WHERE INDICATED, IF EACH VERIFICATION IS NOT NOTED OTHERWISE. IT WILL BE ASSUMED TO BE CORRECT AS SHOWN.

REV	DATE	BY	DESCRIPTION	FOR FABRICATION	FOR PURCHASING	FOR APPROVAL	DWG STATUS	DATE
B	4/14/03	ADI	REVISED DIM					
A	3/31/03	ADI	FOR APPROVAL					

MOODY GARDENS
 ART GLASS RIBBON SCULPTURE
 GALVESTON, TX

DESIGNER: Design Trends, Inc. ADI / ANGLE DETAILING, INC.
 CONTRACTOR: Gilbane Building Co. ADI JOB# 2003-265

SAVOY STUDIOS
 611 N TILLAMOOK ST PORTLAND, OR 97227
 Phone: 503.282.5095 FAX: 282.2183

DRAWN BY: KP
 CHECK BY: ADI
 JOB NO: 02-178
 DWG NO: SPA-2